



# DETOUR GOLD™

## Detour Lake Mine

### NI 43-101 Technical Report



Effective Date:

February 4, 2014

PREPARED BY:

**BBA**

IN COOPERATION WITH:

**SGS**

## Table of Contents

<b>1.0</b>	<b>Executive Summary</b> .....	<b>1-1</b>
1.1	Introduction.....	1-1
1.2	Property Description and Location .....	1-2
1.3	Geology and Mineralization .....	1-2
1.4	Exploration and Drilling Activities .....	1-3
1.5	Drilling, Quality Control, and Data Verification .....	1-3
1.6	Mineral Processing and Metallurgical Testing .....	1-3
1.7	Mineral Resources .....	1-6
1.8	Mineral Reserves .....	1-7
1.9	Mining Methods .....	1-8
1.10	Recovery Methods .....	1-8
1.11	Project Infrastructure .....	1-9
1.12	Environmental and Aboriginal Matters .....	1-10
1.13	Capital and Operating Costs .....	1-12
1.14	Economic Analysis .....	1-13
1.15	Interpretations and Conclusions .....	1-15
1.16	Recommendations .....	1-16
<b>2.0</b>	<b>Introduction</b> .....	<b>2-1</b>
2.1	Purpose and Terms of Reference .....	2-1
2.2	Units and Currency.....	2-1
2.3	Inspection of Property .....	2-1
<b>3.0</b>	<b>Reliance on Other Experts</b> .....	<b>3-1</b>
3.1	Disclaimer.....	3-1
<b>4.0</b>	<b>Property Description and Location</b> .....	<b>4-1</b>
4.1	Location and Access .....	4-1
4.2	Property Ownership and Agreements .....	4-1
4.3	Summary of NSR or Other Obligations .....	4-4
4.4	Current Environmental Obligations .....	4-4
4.5	Permits in Place .....	4-5
<b>5.0</b>	<b>Accessibility, Climate, Local Resources, Infrastructure, and Physiography</b> .....	<b>5-1</b>
5.1.1	Accessibility .....	5-1
5.2	Climate and Physiography .....	5-1
5.3	Local Resource and Infrastructure .....	5-1
<b>6.0</b>	<b>History</b> .....	<b>6-1</b>
6.1	Ownership History .....	6-1

6.2	Exploration History .....	6-2
6.3	Previous Mineral Resource and Reserve Estimates .....	6-4
6.3.1	Detour Lake .....	6-4
6.3.2	Block A .....	6-7
<b>7.0</b>	<b>Geological Setting and Mineralization .....</b>	<b>7-1</b>
7.1	Regional Geology .....	7-1
7.2	Detour Lake Mine and Block A Stratigraphy.....	7-6
7.3	Metamorphism and Alteration .....	7-9
7.4	Structural Geology.....	7-10
7.5	Mineralization .....	7-11
7.5.1	General Characteristics of the Gold Mineralization .....	7-11
7.5.2	Gold Mineralization at the Detour Lake Mine .....	7-12
7.5.3	Gold Mineralization at the Block A Deposit .....	7-14
<b>8.0</b>	<b>Deposit Types .....</b>	<b>8-1</b>
<b>9.0</b>	<b>Exploration .....</b>	<b>9-1</b>
9.1	Background .....	9-1
9.1.1	MMI Geochemical Surveys.....	9-1
9.1.2	IP Geophysical Surveys .....	9-1
9.1.3	Geological Field Mapping and Interpretation.....	9-1
<b>10.0</b>	<b>Drilling Programs.....</b>	<b>10-1</b>
10.1	Detour Lake Deposit.....	10-2
10.2	Block A Deposit .....	10-3
10.3	Exploration Drilling Programs .....	10-3
10.4	Other Drilling Programs .....	10-4
10.5	Drill Hole Survey and Drill Core Recovery.....	10-4
10.6	Mine Grid.....	10-6
<b>11.0</b>	<b>Sample Preparation, Analyses, and Security .....</b>	<b>11-1</b>
11.1	Core Sampling Procedures and Securities.....	11-1
11.2	Analytical Laboratories .....	11-3
11.3	Sample Preparation and Analysis .....	11-4
11.3.1	Sample Preparation and Analysis for Historic Data.....	11-4
11.3.2	Sample Preparation.....	11-4
11.3.3	Gold Analysis for Detour Lake.....	11-5
11.3.4	Gold Analysis for Block A .....	11-6
11.3.5	Gold Analysis for Regional Exploration .....	11-6
11.4	Specific Gravity .....	11-7
11.5	Quality Assurance and Quality Control Procedure .....	11-8
11.5.1	QA/QC Procedures Prior to 2007 .....	11-8
11.5.2	QA/QC Procedures from 2007 to 2011 .....	11-9
11.5.3	QA/QC Procedures for Block A Prior to 2012.....	11-10

11.5.4	QA/QC Procedures for Block A in 2012 .....	11-11
11.6	Conclusion.....	11-19
<b>12.0</b>	<b>Data Verification .....</b>	<b>12-1</b>
12.1	Drill Hole Database Verification.....	12-1
12.2	Database Verification of Historic and Detour Gold Drill Hole Data.....	12-1
12.2.1	Kallio 2005 – 2006 Verification Program .....	12-1
12.2.2	Scott Wilson RPA 2009 Database Verification Program .....	12-2
12.3	SGS Geostat 2009 Database Verification Program .....	12-4
12.4	SGS Geostat 2010 Database Verification Program .....	12-5
12.5	SGS Geostat 2011 Database Verification Program .....	12-6
12.6	SGS Geostat 2012 Detour Drill Hole Database Verification Program .....	12-6
12.7	Final Drill Hole Database.....	12-11
12.8	Summary and Recommendations .....	12-13
<b>13.0</b>	<b>Mineral Processing and Metallurgical Testing .....</b>	<b>13-1</b>
13.1	Sample Selection and Preparation .....	13-1
13.2	Comminution Test Work .....	13-1
13.2.1	Circuit Simulation.....	13-2
13.3	Metallurgical Test Work.....	13-3
13.4	Recovery Estimates .....	13-8
13.5	Estimated Recovery for the Life of Mine.....	13-11
13.6	Update of Recovery Model .....	13-12
13.7	Comparison CIP versus CIL.....	13-13
13.8	Modeling Carbon-in-Pulp (CIP) .....	13-13
13.9	Thickening and Rheology .....	13-13
13.10	Cyanide Destruction .....	13-13
13.11	Reagents .....	13-14
13.12	Selected Process .....	13-15
13.13	Metallurgical Testing on Block A .....	13-16
13.13.1	2010 Metallurgical Test Work.....	13-16
13.13.2	2012-2013 Comminution and Metallurgical Test Work.....	13-17
13.14	Conclusion.....	13-21
<b>14.0</b>	<b>Mineral Resource Estimates .....</b>	<b>14-1</b>
14.1	Introduction.....	14-1
14.2	Detour Lake Mine Resource Estimates.....	14-3
14.2.1	Detour Lake Mine Data.....	14-3
14.2.2	Detour Lake Mine Geological Interpretation .....	14-3
14.2.3	Detour Lake Mine Capping.....	14-5
14.2.4	Detour Lake Mine Composites .....	14-8
14.2.5	Detour Lake Mine Spatial Analysis.....	14-10
14.2.6	Detour Lake Mine Resource Block Modeling .....	14-11

---

14.2.7	Detour Lake Mine Block Grade Interpolation.....	14-14
14.2.8	Detour Lake Mine Mineral Resources Classification .....	14-20
14.2.9	Detour Lake Mine In-Pit Mineral Resources.....	14-21
14.3	Block A Resource Estimate .....	14-23
14.3.1	Block A Data.....	14-23
14.3.2	Block A Geological Interpretation .....	14-24
14.3.3	Block A Capping.....	14-25
14.3.4	Block A Composites .....	14-28
14.3.5	Block A Spatial Analysis .....	14-29
14.3.6	Block A Resource Block Modeling.....	14-31
14.3.7	Block A Block Grade Interpolation.....	14-33
14.3.8	Block A Mineral Resource Classification .....	14-37
14.3.9	Block A In-Pit Mineral Resources .....	14-39
<b>15.0</b>	<b>Mineral Reserve Estimates .....</b>	<b>15-1</b>
15.1	Reserve Block Model .....	15-2
15.2	Pit Optimization .....	15-2
15.2.1	Grade Data .....	15-3
15.2.2	General Pit Slope .....	15-3
15.2.3	Mining Dilution .....	15-3
15.2.4	Costs and Gold Price.....	15-3
15.2.5	Mill Recovery .....	15-3
15.2.6	Mill Cut-off Grade .....	15-4
15.3	Pit Optimization Results .....	15-5
15.4	Engineered Pit Design Parameters .....	15-5
15.4.1	Geotechnical Considerations and Bench Configuration .....	15-5
15.4.2	Final Ramp Design .....	15-7
15.5	Pit Design Results .....	15-8
15.6	Mining Dilution and Mining Loss Evaluation.....	15-9
15.7	Reserve Statement.....	15-9
<b>16.0</b>	<b>Mining Methods .....</b>	<b>16-1</b>
16.1	Introduction.....	16-1
16.2	Mine Production Plan .....	16-1
16.2.1	Annual Mine Plan Results .....	16-1
16.2.2	End-of-Period Mine Production Plans 2012 – 2035 .....	16-5
16.2.3	Overburden and Waste Rock Disposal Areas .....	16-21
16.2.4	Mineralized Waste Stockpile .....	16-23
16.3	Mining Equipment Selection.....	16-23
16.3.1	Primary Equipment Operating Times .....	16-24
16.3.3	Equipment Availability and Utilization.....	16-25
16.3.5	Drilling.....	16-26
16.3.7	Blasting.....	16-27
16.3.8	Loading.....	16-28
16.3.10	Hauling .....	16-29