

**43-101 TECHNICAL REPORT,
UPDATED MINERAL RESERVE ESTIMATE FOR TIMMINS WEST MINE,
TIMMINS, ONTARIO, CANADA**

NTS: 42-A-05,
Longitude: 81.55° West, Latitude: 48.32° North
UTM (NAD 83, Zone17): 458,915m East, 5,359,043 North

PREPARED FOR:

LAKE SHORE GOLD CORP.
181 University Ave, Suite 2000
Toronto, Ontario, Canada, M5H 3M7



Prepared by: Eric Kallio, P. Geo.
Natasha Vaz, P. Eng.

Date: March 31, 2014

Effective Date: February 21, 2014

TABLE OF CONTENTS

CAUTIONARY NOTE.....	x
1.0 SUMMARY.....	1
2.0 INTRODUCTION.....	8
2.1 LIST OF QUALIFIED PERSONS	8
2.2 UNITS AND CURRENCY.....	8
2.3 LIST OF ABBREVIATIONS	9
2.4 DEFINITIONS.....	12
2.4.1 Mineral Resource.....	12
2.4.2 Inferred Mineral Resource.....	12
2.4.3 Indicated Mineral Resource.....	12
2.4.4 Measured Mineral Resource.....	12
2.4.5 Mineral Reserve.....	13
2.4.6 Probable Mineral Reserve	13
2.4.7 Proven Mineral Reserve.....	13
2.5 GLOSSARY	13
2.5.1 General Glossary.....	13
2.5.2 Lake Shore Gold Terminology.....	15
3.0 RELIANCE ON OTHER EXPERTS.....	16
4.0 PROPERTY DESCRIPTION AND LOCATION.....	19
4.1 PROPERTY DESCRIPTION.....	19
4.2 LOCATION	23
4.3 RECENT OWNERSHIP HISTORY AND UNDERLYING AGREEMENTS.....	25
4.4 PAST MINING ACTIVITY, ENVIRONMENTAL LIABILITIES AND PERMITTING.....	26
5.0 ACCESSIBILITY, CLIMATE, LOCAL RESOURCES, INFRASTRUCTURE AND PHYSIOGRAPHY	28
5.1 ACCESSIBILITY	28
5.2 CLIMATE.....	28
5.3 LOCAL RESOURCES AND INFRASTRUCTURE.....	28
5.4 PHYSIOGRAPHY.....	29
6.0 HISTORY	31
6.1 PRIOR OWNERSHIP	31
6.2 GENERAL HISTORY	31
6.3 HISTORICAL RESOURCE ESTIMATES.....	35
6.3.1 Historically Significant Resource Estimates	35
6.3.2 Resource Estimates Reported in Accordance with NI 43-101 and Estimated by a QP	35
6.4 HISTORIC PRODUCTION	38
7.0 GEOLOGICAL SETTING AND MINERALIZATION	39
7.1 REGIONAL GEOLOGY AND STRUCTURE	39
7.2 PROPERTY GEOLOGY.....	43
7.2.1 Timmins Mine Portion of the Timmins West Mine	43
7.2.2 Thunder Creek Portion of the Timmins West Mine.....	44
7.3 STRUCTURAL GEOLOGY	47
7.4 MINERALIZATION	48

TABLE OF CONTENTS

8.0	DEPOSIT TYPES	61
9.0	EXPLORATION	63
9.1	GENERAL OVERVIEW.....	63
9.1.1	Timmins Deposit	64
9.1.2	Thunder Creek Deposit	66
10.0	DRILLING	69
10.1	HISTORICAL DRILLING ON THE TIMMINS WEST MINE PROPERTY	69
10.2	DRILLING ON THE TIMMINS DEPOSIT PROPERTY COMPLETED BY LSG	71
10.3	DRILLING ON THE THUNDER CREEK PROPERTY BY LSG	71
11.0	SAMPLING PREPARATION, ANALYSIS AND SECURITY	74
11.1	SURFACE DIAMOND DRILL PROGRAMS	74
11.1.1	General Statement.....	74
11.1.2	Core Handling and Logging Protocols	74
11.1.3	Property Grids, Hole Collar and Downhole Attitude Surveys	74
11.1.4	Security	75
11.1.5	Drill Core Sampling Method and Approach, Sample Preparation, Analysis and Analytical Procedures	75
11.2	UNDERGROUND DIAMOND DRILL PROGRAM	78
11.2.1	General Statement.....	78
11.2.2	Core Handling and Logging Protocols	78
11.2.3	Property Grids, Hole Collar and Downhole Attitude Surveys	79
11.2.4	Security	80
11.2.5	Underground Diamond Drill Core Sampling Protocols	80
11.2.6	Underground Diamond Drill Core Sample Preparations and Analytical Procedures	82
11.3	UNDERGROUND FACE CHIP CHANNEL AND MUCK SAMPLES	84
11.3.1	Procedure for Taking Face Chip Channel Samples.....	84
11.3.2	Procedure for Taking Muck Samples	84
11.3.3	Security	85
11.3.4	Data Management for Chips and Muck Samples	85
11.4	DATA MANAGEMENT FOR SURFACE AND UNDERGROUND DIAMOND DRILL PROGRAMS	85
11.4.1	Accuracy Analysis - Standards and Blanks	85
11.4.2	Precision Analysis – Duplicates	86
11.4.3	Reporting and Plotting	86
11.5	CHECK ASSAY PROGRAM	87
11.5.1	General Statement.....	87
11.5.2	Procedures	87
11.6	DISCUSSION	87
12.0	DATA VERIFICATION.....	89
12.1	Database Validation	89
13.0	MINERAL PROCESSING AND METALLURGICAL TESTING.....	91
13.1	HISTORICAL TEST WORK	91
13.2	RECENT TEST WORK.....	91

TABLE OF CONTENTS

14.0	MINERAL RESOURCE ESTIMATES	93
14.1	SUMMARY.....	93
14.2	ESTIMATION METHOD	94
14.2.1	Procedures Summary.....	94
14.2.2	Database	95
14.2.3	Mineralized Domains	96
14.2.4	Grade Capping	99
14.2.5	Assay Compositing	104
14.3	SPECIFIC GRAVITY.....	105
14.4	VARIOGRAPHY.....	106
14.5	BLOCK MODEL MINERAL RESOURCE MODELING	109
14.5.1	General.....	109
14.5.2	Block Model Parameters.....	109
14.5.3	Grade Interpolation	109
14.6	BLOCK MODEL VALIDATION.....	111
14.7	MINERAL RESOURCES AND CLASSIFICATION	117
14.7.1	General.....	117
14.7.2	Mineral Resources	117
14.8	RECONCILIATION TO PREVIOUS RESOURCE TIMMINS DEPOSIT.....	122
14.9	ADDITIONAL DRILL HOLE INFORMATION	126
15.0	MINERAL RESERVE ESTIMATES	128
15.1	CUT-OFF GRADE.....	128
15.2	TIMMINS DEPOSIT RESERVE ESTIMATE	129
15.3	THUNDER CREEK DEPOSIT RESERVE ESTIMATE	130
15.4	TIMMINS WEST MINE COMBINED RESERVES	131
16.0	MINING METHODS.....	132
16.1	UNDERGROUND ACCESS.....	136
16.1.1	Primary / Secondary Access.....	136
16.2	SHAFT AND HOISTING FACILITIES	136
16.2.1	Hoisting Plant.....	136
16.2.2	Shaft Services.....	137
16.2.3	Ore / Waste Handling System and Loading Pocket	137
16.3	STOPING METHODS	137
16.3.1	Timmins Deposit	137
16.3.2	Thunder Creek Deposit	139
16.4	RESOURCE ANALYSIS (DILUTION AND RECOVERY)	141
16.4.1	Mining Dilution and Recovery	141
16.4.2	Stopes Cut-Off Grade	142
16.4.3	Timmins Deposit Reserve Estimate	142
16.4.4	Thunder Creek Deposit Reserve Estimate	144
16.4.5	Timmins West Mine Combined Reserves	145
16.5	HAULAGE.....	145
16.5.1	Timmins Deposit Underground Truck Haulage.....	146
16.5.2	Thunder Creek Deposit Underground Truck Haulage.....	146
16.6	DEVELOPMENT	146
16.6.1	Timmins Deposit	148
16.6.2	Thunder Creek Deposit	150

TABLE OF CONTENTS

16.6.3	Ground Support	151
16.7	DEVELOPMENT SCHEDULES.....	151
16.8	BACKFILL	152
16.9	PRODUCTION	152
16.9.1	Timmins Deposit Production	152
16.9.2	Thunder Creek Deposit Production	152
16.9.3	Timmins West Mine Production	153
16.10	PRODUCTION EQUIPMENT	154
16.11	VENTILATION	154
16.11.1	Timmins Deposit Ventilation	154
16.11.2	Thunder Creek Ventilation.....	155
16.11.3	Mine Air Heating and Cooling.....	156
16.12	PERSONNEL.....	156
16.13	UNDERGROUND MINE SERVICES	158
16.13.1	Electrical Distribution and Communications	158
16.13.2	Compressed Air.....	158
16.13.3	Service Water.....	159
16.13.4	Mine Dewatering	159
16.13.5	Roadbed Material	159
16.14	MATERIALS SUPPLY.....	159
16.15	MAINTENANCE.....	160
16.16	SAFETY.....	160
16.17	GEOTECHNICAL	160
16.18	BELL CREEK TAILINGS FACILITY	162
17.0	RECOVERY METHODS.....	165
17.1	HISTORY	165
17.2	BELL CREEK MILL PROCESS DESCRIPTION	165
17.3	METALLURGICAL BALANCE	166
18.0	PROJECT INFRASTRUCTURE	168
18.1	TIMMINS WEST MINE SITE.....	168
18.2	BELL CREEK MILL SITE	168
19.0	MARKET STUDIES AND CONTRACTS	169
20.0	ENVIRONMENTAL STUDIES, PERMITTING AND SOCIAL OR COMMUNITY IMPACT	170
20.1	REGULATORY AND FRAMEWORK	170
20.1.1	Provincial Environmental Assessments	170
20.1.2	Federal Environmental Assessments.....	170
20.1.3	Provincial Permits	170
20.1.4	Federal Permits.....	171
20.2	ENVIRONMENTAL IMPACTS.....	172
20.3	ENVIRONMENTAL MONITORING PROGRAM	173
20.4	HAZARDOUS MATERIALS HANDLING.....	175
20.5	SPILL AND EMERGENCY RESPONSE PLAN	175
20.6	CLOSURE PLANNING	175
20.7	CONSULTATION.....	176
21.0	CAPITAL AND OPERATING COSTS	177
21.1	CAPITAL COSTS.....	177